



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 30 1972  
5-30-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Rankin of Sage Drig. Co. has this

date requested permission to plug the following described well:

Mr. Rankin guarantees payment of the plugging fee.

Operator's full Name: The Pickens Co. Inc.

Complete Address: 800 Preston Bank Bldg. Dallas, TX

Lease Name: Antrim Well No. 1

Location: NE/SE/SW Sec 30 Twp 32s Rge. 8 (E)(W)W

County: Harper Total Depth 4793 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Rankin was instructed to plug the well as follows:

289 ft 8 5/8 surface pipe cemented with 225 sacks. Pump

40 sacks cement to 300 ft. Mud to 40 ft, plug, 1/2 sack

hulls, 15 sacks cement to surface. 5 sacks cement in rat

hole.

Pumped by Halliburton Cementing Co. Great Bend, Ks

Very truly yours,

Conservation Division Agent