

State of Kansas



15-077-20273-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wenrick of Lario Oil & Gas has this date requested permission to plug the following described well:

Mr. Wenrick guarantees payment of the plugging fee.

Operator's full Name: Lario Oil & Gas Co

Complete Address: 301 S Market Wichita, KS

Lease Name: Wilson Well No. 1-A

Location: NW/SW/SE Sec 23 Twp. 32S Rge. 8 (E)(W) W

County: Harper Total Depth 4510 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wenrick was instructed to plug the well as follows:
228 ft 8 5/8 surface cemented with 200 sacks. Fill hole
to 200 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud to
40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

A. Russell Burtin
Conservation Division Agent