

1040987 7-25
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 007-20,234-0001
C SW NW, SEC. 11, T 30 S, R 12 W/E
1980 feet from N ~~S~~ section line
660 feet from W ~~E~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5047

Lease Name Hamilton Well # 1

Operator: Rupe Oil Company, Inc.

County Barber 115.54

Name & Address P.O. Box 783010

Well Total Depth 3555 feet

Wichita, KS 67278-3010

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 287

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: Day: 25 Month: 7 Year: 19 95

Plugging proposal received from Joe

(company name) Duke Drilling Company (phone) 316-267-1331

Work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 740' with 50 sx cement, 2nd plug at 315' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 07 1995

BRINSON
WICHITA, KANSAS

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:30 p.m Day: 25 Month: 7 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 740' with 50 sx cement,

2nd plug at 315' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 65/35 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If old invoice) observe this plugging.

DATE 8-4-95

WELL NO. 43257

7-25

Signed Stephen J. Pfeifer (TECHNICIAN)