

1060247

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,829-00-00

E/2 NE NE, SEC. 7; T 30 S, R 12 W/2
660 feet from N/8 section line
330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Rose Well # 1-7

Operator: F. G. Holl

County Barber

Name & Address 6427 East Kellogg

Well Total Depth 4772 155.09 feet

Wichita, KS 67207

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 264

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sterling Drilling Co. License Number 5142

Address P. O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 4:00 pm Day: 5 Month: June Year: 19 84

Plugging proposal received from Tom Myers

(company name) Sterling (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 4770' with 50 sx cement

2nd plug at 740' with 40 sx cement

3rd plug at 310' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement. Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:30 pm Day: 5 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4770' with 50 sx cement, 2nd plug at 740' with 40 sx cement, 3rd plug at 310' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 07 1984

Remarks: Used 60/40 Pozmis 2% gel 3% cc by Halliburton
(If additional description is necessary, use BACK of this report)

CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luthi
(TECHNICIAN)

INVOICED

DATE 6-15-84

INV NO. 2029 65