

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-2094/00-00

5 1/4 SEC. 1, T. 30S, R. 12 W

SESESW

FEET FROM N/S SECTION LINE

R

TECHNICIAN'S PLUGGING REPORT

FEET FROM W/E SECTION LINE

OPERATOR LICENSE # 8144

LEASE NAME Bar Kumborg WELL # 1

OPERATOR: Gunner Oil Co.  
NAME & ADDRESS 519 Parke  
Pratt Kans 67124

COUNTY Barber

WELL TOTAL DEPTH 2830 <sup>591.98</sup> FEET

CONDUCTOR PIPE: SIZE 4 1/2 FEET 2830

SURFACE CASING: SIZE 8 5/8 FEET 280

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL  INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR W. L. Kirkman Inc. LICENSE NUMBER 5673

ADDRESS 453 S. Well Rd. Box 18611 Wichita Kans 67207

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 30 MONTH: 6 YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM Carl Kumborg

(COMPANY NAME) Gunner Oil Co (PHONE) \_\_\_\_\_

WERE: 1st sandbed off bottom w/ 50' sand & dumped 5 bbls cent on top of sand through bailer, 2nd plug squeezed w/ 3 bbls hulls 15 bbls gells 70 bbls cent & 10 bbls gells & 1 bbl hulls & released rubber plug & 130 bbls cent. The cementing accomplished by Allied Cementing w/ 60/40 prop w/ 2 1/2 gells 3% CC

PLUGGING PROPOSAL RECEIVED BY Paul A. Luttie (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 12:00 AM DAY: 30 MONTH: 6 YEAR: 19 83

ACTUAL PLUGGING REPORT This hole plugged as proposed. Max pressure w/ 500# Shut in pressure w/ 100#

REMARKS: They perforated the 4 1/2" @ 2700' to 50'. They recovered 2000' of 4 1/2" pipe.

I (DID / DID NOT) OBSERVE THIS PLUGGING.

RECEIVED SIGNED  
STATE CORPORATION COMMISSION

Paul A. Luttie (TECHNICIAN)

INVOICED

JUL 05 1983

FORM CP-2/3  
REV. 6-83

DATE 7-12-83

CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 4804-D