

11-26 15-007-16710-00-00

To: 1 040489
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 - Drill Completion Date 5/21/62

SE NE, SEC. 35, T 34 S, R 13 W/X
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3048

Lease Name Ed Sterling Well # 4

Operator: Bristol Resources Corporation
Name & Address: 6655 South Lewis, Suite 200
Tulsa, OK 74136

County Barber 159.31

Well Total Depth 4902 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 238

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Medicine Lodge, KS

Company to plug at: Hour: 2:30 p.m. Day: 26 Month: 11 Year: 19 90

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4901' w/70 sx cement, PRTD 4900', Perfs at 4839-50'

1st plug sand back from 4900' to 3800' and put 5 sx cement on top of sand bridge
through bailer,

2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, and 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 26 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back from 4900-3800' and put 5 sx cement on top
of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, and 100 sx cement.

No wiper plug, surface pipe plated with collar.

Maximum pressure 400 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2900' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED to serve this plugging.

DATE 12-7-90

INV. NO. 30186

Signed Stephen J. Pfeifer
(TECHNICIAN)

STATE CORPORATION COMMISSION
DEC 12-4-90