

1-22-89

1 051122

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,218-00-00
NE NW, SEC. 16, T 30 S, R 13 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 3536

Operator: Ramco Energy Corporation
Name & Address 127 Lee Street
P.O. Box 99
Belpre, OH 45714

4620 feet from S section line
3300 feet from E section line

Lease Name K.D. Lemon Well # 1
County Barber 149.57

Well Total Depth 4602 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1050
13 3/8 125

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 22 Month: 1 Year: 19 89

Plugging proposal received from Harvey Moore

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1100' with 50 sx cement, 2nd plug at 500' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:15 a. Day: 22 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1100' with 50 sx cement,

2nd plug at 500' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement,

Water well plugged with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO.
(If additional description is necessary, use BACK of this form.)

INVOICED
To be used to serve this plugging.

DATE 1-27-89

INV. NO. 23805

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1989
1-26-89
CONSERVATION DIVISION
Wichita, Kansas