

1 20905

7-21

-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200, COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,218-A
C NE NW, SEC. 16, T 30 S, R 13 W
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5506
Operator: Woolsey Petroleum Corp.
Name & Address 107 N. Market, Ste. 600
Wichita, KS 67202

Lease Name Lemon Well # 1-A
County Barber
Well Total Depth 4754 154.50 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1080

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Shawnee Well Service, Inc. License Number 30346
Address 611 N. Blaine, Attica, KS 67009

Company to plug at: Hour: 10:30 a.m. Day: 21 Month: 7 Year: 19 93

Plugging proposal received from Carl Durr
(company name) Woolsey Petroleum Corp. (phone) 316-478-2890

were: 5 1/2" at 4754' w/125 sx cement, PBSD 4650', Perfs at 4690-4700, 4688-93, 4554-84'
1st plug set CIBP at 4488' and dump 2 sx cement on top.
2nd plug pump in 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11:30 a.m. Day: 21 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4488' and dumped 2 sx cement on top of sand through
bailer,
2nd plug pumped in 8 5/8" surface with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3794' of 5 1/2" casing.
If additional description is necessary, use BACK of this form.

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1993

INVOICED

(did / did not observe this plugging.

DATE AUG 03 1993

Signed Duane Parker
(TECHNICIAN)

INV. NO. 38240