

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22414-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 15-30S-13W  
1696 feet from S Section Line, 1699 feet from E Section Line  
Lease/Unit Name: STANNARD Well Number: 1-15  
County: BARBER Total Vertical Depth: 4765 feet

Operator License No.: 31629  
Op Name: NASH OIL & GAS, INC.  
Address: 30060 N. 281 HIGHWAY  
PRATT, KS 67124

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 13.375 feet: 219 WITH 250 SX CMT  
Production: Size 4.5 feet: 4765 WITH 225 SX CMT  
Liner: Size \_\_\_\_\_ feet: 8154.86

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/27/2001 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND BACK TO 4300' & 4 SX CMT ON TOP. PUMP DOWN 13 3/8" 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 135 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/27/2001 10:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4726'. PERFS AT 4394-4459 (6 SETS). SANDED BACK TO 4300' AND PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PUMPED DOWN 13 3/8" SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 135 SX CMT. MAXIMUM PRESSURE 250#. SHUT IN PRESSURE 100#. \*NOTE: LEFT OUT 13 3/8" WIPER PLUG DUE TO 13 3/8" SURFACE PIPE POOR BOYED BACK TO 8 5/8".

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2400' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED

INVOICED

AUG 29 2001

AUG 31 2001

DATE

8-31-01

KCC WICHITA

INV. NO.

2002060321

FOR COPY 2/3

MP