

1 030453

15-007-20403-00-00

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Not Available

NE NE SE, SEC. 21, T 30 S, R 13 W/E  
2310 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050  
Originally belonged to Texas Energies, Inc.  
Operator: Kelso Casing Pulling  
Name & Address: P. O. Box 347  
Chase, KS 67524

Lease Name Lemon Well # 1  
County Barber 143.10  
Well Total Depth 4403 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 10 3/4 feet 361

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:00 am Day: 19 Month: June Year: 19 85

Plugging proposal received from Bill Fulls  
(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4280' PBD 4403' Perfs at 4203-4204'

1st plug pump 60 sx cement to bottom  
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, 2 sx hulls  
and 150 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 9:00 am Day: 19 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 60 sx cement to bottom, 2nd plug squeezed well  
with 3 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, 2 sx hulls and 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 01 1985  
7-1-85

CONSERVATION DIVISION  
Wichita, Kansas

Maximum pressure 500 and shut in 200 psi

Remarks: Recovered 2617' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

Jack Luchi observed the plugging  
(old / xxxxxx) observe this plugging.

INVOICED

DATE 7-10-85  
INV. NO. 8819

Signed Steve Durrant  
(TECHNICIAN)