

1 040523

3-5

-00401

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,210A

C NE SW, SEC. 18, T 30 S, R 13 W/E

1980 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lessee Name Rauhut Well # 1

Operator: Raymond Oil Company, Inc.

County Barber 154.37

Name & Address P.O. Box 48788

Well Total Depth 4750 feet

Wichita, KS 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 999

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 5 Month: 3 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4748' with 175 sx cement, Perfs at 4564-94'

1st plug sand back to 4550' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 5 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4510' and dumped 5 sx cement on top of
sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Maximum pressure 800 psi and shut in 500 psi.

Recovered 3600' of 5 1/2" casing.

Remarks: Used 60/40 Pozmix 6% gel by United Cementing & Acid Co., Inc.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 3-15-91

INV. NO. 31190

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAR 11 1991