

To: 1 040696 9-15
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,199-~~X~~ ⁰⁰⁻⁰² 67
C NE NW, SEC. 17, T 30 S, R 13 W/4
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5506
Operator: Woolsey Petroleum Corporation
Name & Address: 107 N. Market, Suite 600
Wichita, KS 67202

Lease Name Lemon "C" Well # 1
County Barber
Well Total Depth 4780 155.35 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 1:50 p.m. Day: 8 Month: 9 Year: 19 92

Plugging proposal received from Carl Durr
(company name) Woolsey Petroleum (phone) 316-267-4379

were: 4 1/2" at 4778' w/165 sx cement, Perfs at 4610'-4630'
1st plug sand back to 4241' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1992
9-21-92
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Steve Durrant

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 15 Month: 9 Year: 19 92

ACTUAL PLUGGING REPORT 9/8/92 witnessed by Steve Durrant:

1st plug sanded back to 4241' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped down 8 5/8" with 3 sx hulls, 10 sx gel, 50 sx cement, 10 gel, 1 sx hulls,
released 8 5/8" wiper plug and pumped 125 sx cement. Cement fell.

9/15/92 witnessed by Steve Pfeifer. Pratt Well Service was rigged up over hole. Tagged
top of cement at 373' KB with tubing. (See back)

Remarks: Used 60/40 Pozmix 6% gel and common cement w/3% cc by B.J. Services. Recovered 3200

Additional description is necessary, use BACK of this form.) of 4" casing

1 (did / observe this plugging.

DATE: 10-7-92

INV. NO. 36361

Signed Steve Pfeifer
(TECHNICIAN)