

1090947

TO: STATE CORPORATION COMMISSION

8-18

API NUMBER 15-007-22,574-0000
E2 SW NW SW SEC. 3, T 33 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 1660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 430 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MAGNISON TRUST WELL # A-1

TECHNICIAN'S PLUGGING REPORT COUNTY BARBER 167.70

OPERATOR LICENSE # 5506 WELL TOTAL DEPTH 5160 FEET

OPERATOR: WOOLSEY PETROLEUM CORP PRODUCTION CSG: SIZE FEET

NAME AND 125 NORTH MARKET, STE 1000 SURFACE CASING: SIZE 10 3/4" FEET 223'

ADDRESS WICHITA, KS 67202-1775

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ABERCROMBIE DRILLING LICENSE NUMBER 30606

ADDRESS 150 N. MAIN, STE 801 WICHITA, KS 67202-1383

COMPANY TO PLUG AT: HOUR: 5:00 AM DAY: 18 MONTH: 08 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM TONY

(COMPANY NAME) ABERCROMBIE DRILLING (PHONE) 316-262-1841

WERE:

1ST PLUG AT 600' WITH 50 SX CEMENT, 2ND PLUG AT 250' WITH 70SX CEMENT,

3RD PLUG AT 40' WITH 15 SX CEMENT, 4TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

5TH PLUG TO CIRCULTE MOUSEHOLE WITH 10 SX CEMENT.

8-26-98
STEVE MIDDLETON
316-262-1841

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 8:00 AM DAY: 18 MONTH: 08 YEAR: 1998

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 600' WITH 50 SX CEMENT, 2ND PLUG AT 250' WITH 70 SX CEMENT,

3RD PLUG AT 40' WITH 15 SX CEMENT, 4TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

5TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4 LB FLO SEAL BY ALLIED
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED (TECHNICIAN) FORM CP-2/3

DATE 8-24-98

INV. NO. 51191

8-18

8-18 JAN 29 1999