

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

R
CPB

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. J-35 County: Barber

Location: CNW SW Sec. 2 Twp. 53 Rge. 13 (E) (W)

Name of Field: _____ Total Depth: 3881

I have this date completed supervision of plugging of:

Lease Name: Weidener Well No. 1

Operator's Full Name: D.W. Skinner

Complete Address: Medicine Lodge, Kans

Plugging Contractor: West Supply Co

Address: Chase Kans. License No. _____

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6 PM Day 12 Month Dec Year 1958

The above well was plugged as follows:

30 1/2' of 8 1/2" surface casing cemented with cement.
Oil string set at 3881'. Top perf 3855'. Hole was filled
to 3845' with sand and 5 sack cement dumped on
sand with dump trailer. Hole filled with rotary
mud to 200'. A 10' rock bridge set to 190' with 20 sk
cement dumped top bridge. Heavy mud to 40'. Rock
bridge set from 40 to 30'. Cement dumped from 30' to
base of collar.

Signed: [Signature]
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

PLUGGING
FILE SEC 2 T 33 R 13W
BOOK PAGE 2 LINE 35

RECEIVED
STATE CORPORATION COMMISSION
DEC 24 1958
12-24-58
CONSERVATION DIVISION
Wichita, Kans