

KANSAS

Form CP-3
Rev. 6-26-62STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION
DEC 14 1967
12-11-67
CONSERVATION DIVISION
WICHITA, KANSASJ. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202Intent to Drill,
filed November 22, 1967.

Operator's Full Name Lee Phillips Oil Company
Complete Address: 1532 Wichita Plaza Bldg., Wichita, Kansas 67202
Lease Name Blasdel Well No. # 1
Location C NE NE Sec. 16 Twp. 33 Rge. 7 (E) W
County Harper Total Depth 4980'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Sweetman Drilling Company
Address: Box 645, Great Bend, Kansas 67530 License No.
Operation Completed: Hour 12:15AM Day 8th Month December Year 1967

The Above well was plugged as follows:

208' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole was
filled with drilling mud to 200', 1st cementing plug, bridged with 2 sacks
of dry cement and 1/2 sack of hulls on fluid at 200', and cemented with 23
sacks, with cement from 190' to 115'. Hole was filled with drilling mud
to 40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack
of hulls on fluid at 40', and cemented with 9 sacks, with cement from
30' to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 12/11/67
INV. NO. 6871-4