

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Anadarko Prod. Co

Complete Address Box 351 Liberal, KS

Lease Name Frank A Well No. 1

Location 990' FNL & 660' FEL Sec. 16 Twp. 33 Rge. 7 (E) (W) W

County Harper Total Depth 4555

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pratt Well Service

Address 723 S Ninnescah Pratt, KS License No. _____

Operation Completed: Hour 10:00 AM Day 15 Month 6 Year 1974

The above well was plugged as follows:

298 ft 8 5/8 surface cemented with 300 sacks. 4544 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 4506 ft. Pump 20 sacks cement
to 4400 ft. Pulled 3600 ft 5 1/8. Pump 40 sacks cement to 250 ft.
Mud to 40 ft, 10 sacks cement to surface.

Pumped by Halliburton Cementing Co Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 6/19/74

INV. NO. 9331-W