

R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1965
1-4-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name McKenny Well No. # 1

Location C SW SW Sec. 16 Twp. 33 Rge. 8 (E) (W) W

County Harper Total Depth 4993

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita, Kans. License No. _____

Operation Completed: Hour 5:00AM Day 30th Month Dec. Year 1964

The Above well was plugged as follows:

249' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole
was filled with drilling mud to 240', 1st cementing plug, bridged
solid with hulls, and cemented with 25 sacks, through the drill pipe.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with hulls, and cemented with 10 sacks to the base of the cellar.
Rat and mouse hole bridged and cemented with 5 sacks.
This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1-4-65

INV. NO. 469-W