

To: 1 040863
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-30

API NUMBER 15-007-0001-00-00 Completion date 6/8/67
C SW SW, SEC. 29, T 7 S, R 13
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3553
Operator: Citation Oil & Gas Corp.
Name & Address 8223 Willow Place Sq., Ste. 250
Houston, TX 77070-5623

Lease Name J.D. Roberts Well # 1
County Barber 159.25
Well Total Depth 4900 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 380

Abandoned Oil Well Gas Well X Input Well SWD Well O&A
Other well as hereinafter indicated
Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 3 p.m. Day: 30 Month: 6 Year: 19 94
Plugging proposal received from Jeff Uecker
(company name) Citation Oil & Gas Corp. (phone) 405-681-9400

Remarks: 4 1/2" at 4899' w/175 sx cement, PBSD 4857', Perfs at 4812-18', TOC 3900'
Casing leaks in 4 1/2" between 3780-3840'
1st plug spot 90 sx cement at 4840' through tubing,
2nd plug perforate 4 1/2" casing at 700', pump down 4 1/2" casing with 200 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 6 p.m. Day: 30 Month: 6 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug spotted 90 sx cement at 4840' through tubing,
Perforated 4 1/2" casing at 700', Established circulation with water between 4 1/2" X 8 5/8"
annulus.

2nd plug pumped down 4 1/2" casing with 200 sx cement. Cement circulated out of 4 1/2" X 8 5/8"
annulus.

RECEIVED
JUL 08 1994
7-8-94

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED
DATE 7-11-94
INV. NO. 40803

Signed Steve Pfeifer (TECHNICIAN)