

1040765

6-25

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,256-00-01
SE NW SE, SEC. 29, T 34 S, R 13 W
1625 feet from S section line
1650 feet from E section line
Nighswonger A-1

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Operator: Marathon Oil Company

Name & Address: P.O. Box 689

Address: Oklahoma City, OK 73101

Lease Name Barber Well #
County

Well Total Depth 5100 165.75 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 378

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address: P.O. Box 687, Medicine Lodge, KS 67104

Company to plug at: Hour: 9 a.m. Day: 25 Month: 6 Year: 19 93

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

Work: 4 1/2" at 5045' w/150 sx cement, PBTD 5045', Perfs at 4858-76, 4884-4916', CIBP at 4775', Perfs at 4705-09'

1st plug sand back to 4665' and dump 4 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 110 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 9:45 a.m. Day: 25 Month: 6 Year: 19 93
1st plug sanded back to 4655' and dumped 4 sx cement on top of sand

ACTUAL PLUGGING REPORT bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 110 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3100' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED I (did / did not) observe this plugging.

DATE JUL 13 1993

Signed Stephen J. Pfeifer (TECHNICIAN)

WV. NO. 38091

RECEIVED STATE CORPORATION COMMISSION JUN 29 1993 CONSERVATION DIVISION Wichita, Kansas