

To: 1 40766 6-25
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,268-00-00

W/2 E/2 NE, SEC. 29 , T 34 S, R 13 W X
3960 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171
Operator: Marathon Oil Company
Name & Address: P.O. Box 689
Oklahoma City, OK 73101-0689

Lease Name Blunk "A" Well # 1
County Barber
Well Total Depth 5200 169.00 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 382

Abandoned Oil Well _____ Gas Well _____ X Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:30 a.m. Day: 25 Month: 6 Year: 19 93

Plugging proposal received from Jeff Sletto
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5083' w/150 sx cement, PBTD 5050', Perfs at 4844-70'
1st plug sand back to 4790' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, release 8.5/8" wiper plug and pump 110 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Operations Completed: Hour: 11:15 a.m. Day: 25 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4790' and dumped 4 sx cement on top of sand
through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 110 sx cement.
Maximum pressure 100 psi and shut in 0 psi-on slight vacuum.

RECEIVED
STATE CORPORATION COMMISSION
6-29-93
JUN 29 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 4 1/2" casing.
Additional description is necessary, use BACK of this form.

INVOICED
JUL 13 1993
38090

Signed Stephen J. Pfeifer
(TECHNICIAN)