

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,567-0000

SW/4, Sec. 2, T 30 S, R 14 W/K

960 feet from N/S section line

330 feet from W/K section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5420

Lease Name ALEXANDER Well #1-A

Operator: WHITE & Ellis Drilling, Inc
Name & Address 401 E. Douglas - Suite 500
Wichita, KS 67202

County BARBER

Well Total Depth 4620 feet H 150.15

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1045

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Company tools License Number

Address

Company to plug at: Hour: 4:00 AM Day: 24 Month: FEB Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Bob CASPER

(company name) (phone)

were: course 50/50 Pozmix, 4% gel - 3% CC & 1 qt 1st plug @ 1080'
w/50 sy; 2nd plug @ 720' w/40 sy; 3rd plug
@ 40' w/ solid bridge of bulls & 8 5/8 plug; 4th plug
40'-0' w/10 sy; 5th plug by circ. 10 sy in
the rat hole

Signed R. Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 AM Day: 24 Month: FEB Year: 1983

ACTUAL PLUGGING REPORT plugged as ordered.

Cementing by Allied

Remarks: 8 5/8" set w/ 300 sy Halliburton lite & 300 sy 60/40
Pozmix, 3% g - 2% CC
anhydrite top @ 763

I hereby certify that the above plugging instructions were given as herein stated
and that I ~~was~~ / STATE not observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
3-3-83
MAR 3 1983
INVOICED
CONSERVATION DIVISION
Wichita, Kansas

Signed R. Barluttan
(TECHNICIAN)

DATE 3-24-83
INV. NO. 30216-W