

To: 1 090199
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-1
API NUMBER 15-007-22,400-0000
160' S of 2 R

TECHNICIAN'S PLUGGING REPORT

C S/2 SW, SEC. 2, T. 30 S, R. 14 W/E
500 feet from S section line
3960 feet from E section line
Lease Name Alexander Well # 1-2
County Barber 151.93
Well Total Depth 4675 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 13 3/8 feet 234

Operator License # 5056
Operator: F.G. Holl Company
Name & Address P.O. Box 780167
Wichita, KS 67278-0167

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Sterling Drilling Company License Number 5142
Address P.O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 3 a.m. Day: 1 Month: 6 Year: 19 92

Plugging proposal received from Vaughn Thompson
(company name) Sterling Drilling Company (phone) 316-278-2131

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 850'
1st plug at 850' with 50 sx cement,
2nd plug at 260' with 125 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 a.m. Day: 1 Month: 6 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 850' with 50 sx cement,
2nd plug at 260' with 125 sx cement,
3rd plug at 60' with 40 sx cement,
4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

I (Signed) Steve Middleton observe this plugging.

DATE 6-30-92

INV. NO. 35591

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1992
6-5-92
Signed Steve Middleton
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

EFFECTIVE DATE: 5-17-92
DISTRICT # 1
SEAL Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL 007-22,400-0000
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date: May 12, 1992
160' Spot of C S/2 SW Sec 2 Twp 30 S, Rg 14W East 13W West

OPERATOR: License # 5056
Name: F. G. HOLL COMPANY
Address: P.O. BOX 780167
City/State/Zip: Wichita, Kansas 67278-0167
Contact Person: Elwyn H. Nagel
Phone: (316) 684-8481

500' feet from South / North line of Section
3960' feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR

CONTRACTOR: License # 5142
Name: Sterling Drilling Company

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Barber
Lease Name: ALEXANDER Well #: 1-2
Field Name: Clara Ext.

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield ..X Mud Rotary
X Gas ... Storage ..X Pool Ext. ... Air Rotary
... OUVU ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other
... Other

Is this a Prorated/Spaced Field? ... yes X no
Target Formation(s): Lan., Simp. Sand, Arbuckle
Nearest Lease or unit boundary: 500'
Ground Surface Elevation: 1920' Est. feet MSL
Water well within one-quarter mile: ... yes X no
Public water supply well within one mile: ... yes X no
Depth to bottom of fresh water: 130'
Depth to bottom of usable water: 180'
Surface Pipe by Alternate: X.. 1 ... 2
Length of Surface Pipe Planned to be set: 200'
Length of Conductor pipe required: NA

If OUVU: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Projected Total Depth: 4650'
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
X well ... farm pond ... other

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth:
Bottom Hole Location:
Exp. 11/12/92

DNR Permit #: (Applied for by Sterling Drlg.)
Will Cores Be Taken? ... yes X no
If yes, proposed zone:
200' Alt. I Req.

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

- 1. Notify the appropriate district office prior to spudding of well;

Pusher Thompson
SPUD DATE 5-20-92 INIT.
LENGTH SURFACE PLANNED 200 + 13 3/8
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 13 3/8 @ 13 3/8 CONDUCTOR
ANHYDRITE T- B- 850 ELEVATION
TD 4675 FORMATION Halo
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. WT 40 SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 850 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 260 Ft. W/ 125 SX
40' Plug @ 40 Ft. W/ 40 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL 15 SX (Irr. Well Pond Hauling)
TECHNICIAN SM DATE 5-20-92
TYPE OF CEMENT 60/40 670
START TIME 8:00 (AM/PM) DATE 6-1-1992
COMPLETION TIME 5:00 (AM/PM) DATE 6-1-1992
CEMENT COMPANY 17111. buaton