

1 090274

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,983-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Operator: Hummon Corporation
Name & Address: 400 One Main Place
Wichita, KS 67202

NE SW SE, SEC. 21, T 32 S, R 11
990 feet from N/S section line
1650 feet from W/E section line

Lease Name Lukens Trust Well # 1
County Barber 125.13
Well Total Depth 3850 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 227 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Big-H Drilling, Inc. License Number 5148
Address 400 One Main Place, Wichita, KS 67202

Company to plug at: Hour: 9:00 am Day: 12 Month: January Year: 19 85

Plugging proposal received from Jerry Tharp
(company name) Big-H (phone) 316-263-8521

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 810' with 40 sx cement

2nd plug at 270' with 40 sx cement

3rd plug solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by RBF Barlittan (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:45 am Day: 12 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 810' with 40 sx cement, 2nd plug at 270' with 40
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to
circulate mouse hole with 10 sx cement.

STATE CORPORATION COMMISSION

JAN 23 1985
1-23-85
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 1-28-85
NO. 6682

Signed RBF Barlittan (TECHNICIAN)

FEB 18 1985