

To: 1 040905
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-8

API NUMBER 15-007-20,919-0000
SE NE NW, SEC. 19, T 7 S, R 11 W.
4290 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5478
Operator: Graves Drilling Co.
Name & Address P.O. Box 8250
Wichita, KS 67208-8250

Lease Name Bumgardner Well # 2
County Barber
Well Total Depth 3568 115.96 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 216

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 9:15 a.m. Day: 8 Month: 11 Year: 1994

Plugging proposal received from Jeff Sletto
(company name) Clarke Corporation (phone) 316-886-5665

logs: 4 1/2" at 3458' w/75 sx cement, Open hole 3548-3568'
1st plug sand back to 3500' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 5 sx gel, and 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10 a.m. Day: 8 Month: 11 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 3495' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 5 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Maximum pressure 1000 psi and shut in 550 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

11-15-94
NOV 15 1994

INVOICED

DATE 12-5-94
REV. NO. 41784

Signed Stephen J. Durrant
(TECHNICIAN)