

5-6

To: 1 031076
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,296-00-00

S/2 N/2 NE, SEC. 34, T 34 S, R 13 W/EX

4290 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4480

Lease Name Sterling Well # 1

Operator: Blackhawk Exploration, Inc.

County Barber 119.44

Name & Address 200 East First, Suite 100

Well Total Depth 3675 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 1 p.m. Day: 6 Month: 5 Year: 19 90

Plugging proposal received from Harvey Moore

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841
Elevation 1490'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 900'
1st plug at Base Anhydrite or 900' with 50 sx cement,

2nd plug at 360' with 50 sx cement, 3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:30 p.m. Day: 6 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 900' with 50 sx cement,

2nd plug at 360' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-16-90

INV. NO. 28150
5-6

observe this plugging.

5-11-90

Signed Steve Durrant (TECHNICIAN)