

To: 1 040413
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-11
API NUMBER 15- 007-22,302-00-00 110R
C N/2 SW SW SEC. 4, T 30 S, R 13 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 5056
Operator: F.G. Holl Company
Name & Address: P.O. Box 780167
Wichita, KS 67278-0167

990 feet from S section line
4620 feet from E section line
Lease Name Lambert "D" Well # 1-4
County Barber 40.11
Well Total Depth 1234 feet
Conductor Pipe: Size 13 3/8 feet 150
Surface Casing: Size none feet

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Trans-Pac Drilling, Inc. License Number 5841
Address One Main Place, Suite 410, Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 11 Month: 4 Year: 19 90

Plugging proposal received from Gary Pugh
(company name) Trans-Pac Drilling, Inc. (phone) 316-265-0226

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 805-820'
1st plug at 820' with 100 sx cement,
2nd plug at 180' with 100 sx cement,
3rd plug at 40' with 25 sx cement,
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:45 p.m. Day: 11 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 12 1/4" hole 1st plug at 820' with 100 sx cement,
13 3/8" conductor 2nd plug at 180' with 100 sx cement,
3rd plug at 40' with 25 sx cement,
4th plug to circulate rathole with 15 sx cement.

(Got crooked hole, going to skid rig, never had any lost circulation problems.)

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (X) / do observe this plugging.

DATE 4-24-90 4-18-90

Signed Stephen J. Pfeifer
(TECHNICIAN)

INV. NO. 27945
4-11 JUN 21 1990

Must be approved by the K.C.C. five (5) days prior to commencing well

15-007-22, 302-00-00

Expected Spud Date April 9, 1990
month day year

C N/2 SW SW Sec 4 Twp 30 S, Rg 13 East West

OPERATOR: License # 5056
Name: F.G. HOLL COMPANY
Address: P.O. BOX 780167
City/State/Zip: Wichita, Kansas 67278-0167
Contact Person: Elwyn H. Nagel
Phone: (316) 684-8481

990 feet from South line of Section
4620 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License # 5841
Name: TRANS-PAC DRILLING, INC.

County: Barber
Lease Name: Lambert "D"
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:
X Oil Inj Infield X Mud Rotary
X Gas Storage Pool Ext. Air Rotary
OAWO Disposal X Wildcat Cable
Seismic: # of Holes

Is this a Prorated Field? yes X no
Target Formation(s): Miss. Viola
Nearest lease or unit boundary: 660 feet
Ground Surface Elevation: 1896 est. feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 120
Depth to bottom of usable water: 158
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 220'
Length of Conductor pipe required: NA
Projected Total Depth: 4780'
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:

If OAWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

X well farm pond other
DWR Permit #: Trans-Pac will apply
Will Cores Be Taken?: yes X no
If yes, proposed zone:

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

Exp 10-1-90

Req.

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

- 1. The appropriate district office shall be notified before setting surface pipe;
- 2. The minimum amount of surface pipe as specified above shall be set by circulating cement to the top; in all cases surface pipe shall be set through all unconsolidated materials plus a minimum of 20 feet into the underlying formation;

If the well is dry, a plugging proposal shall be submitted to the district office. An agreement between the operator

12 1/4 hole to 1151
7 7/8 hole F10w
PUSHER Gary Sayler
TD 1234. FORMATION
conductor 1378 @ 150'
SURFACE PIPE none @
ANHYDRITE 820 ELEVATION
STARTING TIME & DATE 12:30 P.M. 4-11-90
COMPLETION TIME & DATE 1:45 P.M. 4-11-90
1st PLUG @ 820 FT. W/ 100 SX
2nd PLUG @ 180 FT. W/ 100 SX
3rd PLUG @ 40 FT. W/ 25 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ ~~15~~ ^{100' drilled} SX
WATER WELL PLUGGED W/ Save - SX
CEMENT COMPANY Allied
TECHNICIAN S.P. - 4-11-90
TYPE OF CEMENT 60/40 ppc 60 gal
4-8-90
Set 897 1100'
1378 30 ft.
WINDY TO SKID
GOING TO SKID
GOING

Submit plugging report (CP-4) after plugging is completed;
Obtain written approval before disposing or injecting salt water.