

To: 1052100 API NUMBER 15-007-22,284-00-01  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION SW NW NW NW, SEC. 4, T 30 S, R 13 W/E  
130 S. Market, Room 2078  
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT  
Operator License # 9408  
Operator: Trans Pacific Oil Corporation  
Name & Address: 100 N. Main, Ste. 1000  
Wichita, KS 67202  
Lease Name Lambert C Well # 1-4  
County Barber 155.67  
Well Total Depth 4790 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 293

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901  
Address P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 11 a.m. Day: 2 Month: 1 Year: 19 97

Plugging proposal received from Kent Strube  
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

Work: 4 1/2" at 4789' w/225 sx cement, PBTD 4736', Perfs at 4496-4514, 4578-4613'  
1st plug sand back to 4450' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 a.m. Day: 2 Month: 1 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 4 sx cement on top of sand  
through bailer,

2nd plug pumped down 10 3/4" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, released 10 3/4" wiper plug and pumped 150 sx cement.

Maximum pressure 300 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3600' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

DATE JAN 13 1997  
OBSERVE THIS PLUGGING.

Signed Richard M. Lacey  
(TECHNICIAN)

**INVOICED**  
DATE JAN 13 1997  
INV. NO. 47349