

8-15-88

1 040153

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,144-00-00

SW SW SE, SEC. 4, T 30 S, R 13 W&E

330 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Lambert Well # 1

Operator: Hummon Corporation

County Barber 151.61

Name & Address 400 One Main Place

Well Total Depth 4665 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 15 Month: 8 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers Inc. (phone) 316-793-9711

were: 5 1/2" at 4420' PBSD 4388' Perfs at 4328-32', 4354-4360' Elevation 1876' KB

1st plug pump 30 sx common cement and 100 lbs. hulls,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement

RECEIVED
STATE CORPORATION COMMISSION
8-23-88
AUG 25 1988
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by Gary Burke (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12 p.m. Day: 15 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 100 lbs hulls and 30 sx common cement.

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, 8 5/8" wiper plug and 125 sx cement.

Maximum pressure 100 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1927' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-24-88

INV. NO. 21894

Signed Stephen J. Pfeifer (TECHNICIAN)