

To: 1 040826 2-16
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,134-00-00
NW NW NE, SEC. 1, T. 30 S, R. 13 W/NE
4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5778
Operator: Carl Todd
Name
Address 1117 W. River Blvd.
Wichita, KS 67203

Lease Name Levens Well # 3-1
County Barber
Well Total Depth 4700 152.75 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 241

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 9:15 a.m. Day: 16 Month: 2 Year: 1994
Plugging proposal received from Thom Pool
(company name) Carl Todd (phone) 316-594-2455

Perfs: 4 1/2" at 2913' w/100 sx cement, Perfs at 2784-86'
1st plug sand back to 2690' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4" wiper
plug and pump 150 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

RECEIVED
Plugging Operations attended by STATE CORPORATION COMMISSION Part None
Operations Completed: Hour: 10 a.m. FEB 24 1994 Month: 2 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 2690' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 100 sx cement.
Maximum pressure 300 psi and shut in 150 psi.
Water well plugged with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 900' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE FEB 25 1994
INV. NO. 40044

Signed [Signature] (TECHNICIAN)