

1 050851

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,887-00-00
C NW SE, SEC. 13, T 30 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT

1980 feet from S section line
1980 feet from E section line

Operator License # 8653

Lease Name Heublein Well # 13-1

Operator: Petroleum Technologies, Inc.
Name & Address 3535 Broadway #C
Kansas City, MO 64111

County Barber 14713

Well Total Depth 4527 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 355

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:30 p.m. Day: 20 Month: 10 Year: 19 86

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4524' PBD 4400' Perfs at 4254-4256'

1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 25 sx gel, 50 sx cement, 5 sx gel, and

80 sx cement.

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 20 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200' and dumped 5 sx cement on top of sand through bailer

2nd plug pumped down 8 5/8" with 3 sx hulls, 25 sx gel, 50 sx cement, 5 sx gel, released 8 5/8" wiper plug and pumped 80 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA
10-22-86

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Recovered 2800' of 5 1/2" casing. Used 60/40 Pozmix 6% gel 2% cc by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-22-86 observe this plugging.

Signed Richard W. Lacy
(TECHNICIAN)

DIV. NO. 15213
10-20