

To: 1 040446
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13-007-01,022-00-01

NW SE NW, SEC. 13, T 30 S, R 12 W/E
3630 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5923

Lease Name McEntire Well # 1-A

Operator: American Petroleum Company, Inc.
Name & Address 7701 E. Kellogg, #240
Wichita, KS 67207

County Barber 105.11

Well Total Depth 3234 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains Inc. License Number 4072

Address P.O. Box 346, Ness City, KS 67560

Company to plug at: Hour: 5:45 p.m. Day: 2 Month: 8 Year: 19 90

Plugging proposal received from James T. Barvais

(company name) American Petroleum (phone) 316-686-1635

were: 5 1/2" at 3194' w/210 sx cement, PBD 3194', Perfs at 2754-2757', Elevation 1812' GL

1st plug sand back to 2700' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:30 a.m. Day: 7 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 2689' and dumped 5 sx cement on top of

sand bridge through bailer, 8/2/90-pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, approx. 8 sx gel. Pumped hole in surface pipe. Gel circulated up backside of 8 5/8" surface pipe. Maximum pressure 450 psi and shut in 0 psi. 8/7/90 Hayes Well Service on hole. Tagged top of cement at 150'. Drilled good cement to 160'. Circulated 8 5/8" with cement to surface through tubing (from 160' to surface). Took

40 sx cement to fill.

AUG - 9 1990

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1900' of 5 1/2" casing.
(if additional description is necessary, use **BACK** of this form.)

INVOICED (if applicable) observe this plugging.

DATE AUG 23 1990

INV. NO. 29002

Signed Stephen J. Pfeifer
(TECHNICIAN)