

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22164-00-01
Spot: CW2NWNE Sec/Twnshp/Rge: 13-30S-12W
4620 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: MCINTIRE Well Number: 1
County: BARBER Total Vertical Depth: 4728 feet

Operator License No.: 30265
Op Name: OSPREY OIL & GAS, INC.
Address: PO BOX 3398
ENGLEWOOD, CO 80155

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 262 WITH 160 SX CMT
Production: Size 5.5 feet: 3917 WITH 300 SX CMT
Liner: Size feet: 8153.66

Well Type: GAS UIC Docket No: Date/Time to Plug: 07/10/2001 12:30 PM

Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (316) 886-5665

Proposed Plugging Method: CIBP 2500'. 1ST PLUG AT 700' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/10/2001 1:30 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 2697'. PERFS AT 2784-86'. PERFS AT 2642-46' SQUEEZED WITH 75 SX CMT. PERFS AT 2554-58' SQUEEZED WITH 50 SX CMT. SET CIBP @ 2490' AND PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. RAN 2 3/8" TUBING IN TO SPOT PLUGS THROUGH. LOAD HOLE WITH GEL. 1ST PLUG AT 700' WITH 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED

DATE 7-23-01
INVOICE NO. 2002060099

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 5 1/2" CASING.

Plugged through: TBG

District: 01 KANSAS CORPORATION COMMISSION

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED

JUL 20 2001

CONSERVATION DIVISION

JUL 13 2001

Form CP-2/3

MP