

To: 1 120717
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-9
API NUMBER 15-007-21,984-0001
115' E & 45' S
N/2 SE NE, SEC. 10, T. 30 S, R. 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5030
Operator: Vess Oil Corporation
Name & Address: 8100 E. 22nd St. N, Bldg. 300
Wichita, KS 67226

3585 feet from S section line
545 feet from E section line
Lease Name Gibson Well # 1 OWVO
County Barber
Well Total Depth 4801 ^{156.03} feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 312

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 10 p.m. Day: 8 Month: 7 Year: 19 92

Plugging proposal received from Greg Davidson
(company name) L.D. Drilling, Inc. (phone) 316-793-3051

work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 4650' with 40 sx cement, 2nd plug at 960' with 50 sx cement,
3rd plug at 330' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5 a.m. Day: 9 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 4650' with 40 sx cement,
2nd plug at 960' with 50 sx cement,
3rd plug at 330' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

RECEIVED
STATE CORPORATION COMMISSION

(if additional description is necessary, use BACK of this form)

DATE 7-24-92
I (DATE) did not observe this plugging.

INVOICED
DATE 7-24-92
35792

Signed Duane Rankin
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

JUL 13 1992