

1070143

TO: STATE CORPORATION COMMISSION

API NUMBER 15-007-20,212-0000  
220'SSE OF C SW/4 SEC. 29, T 33 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HOLMES "B" WELL # 1

TECHNICIAN'S PLUGGING REPORT

8/4

COUNTY BARBER 157.40

OPERATOR LICENSE # 9449

WELL TOTAL DEPTH 4843 FEET

OPERATOR: GREAT EASTERN ENERGY & DEV. PRODUCTION CSG: SIZE 5/8" @ 4790' WITH 150 SX

NAME AND ADDRESS 500 W TEXAS, SUITE 955 SURFACE CASING: SIZE 8 5/8" @ 342' WITH 230 SX

MIDLAND, TX 79701

ABANDONED OIL WELL GAS WELL X INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31528

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 04 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

RECEIVED STATE CORPORATION COMMISSION

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

AUG - 8 2000  
8-8-00

WERE: OPEN HOLE AT 4790-4843

CONSERVATION DIVISION  
Wichita, Kansas

1ST PLUG SET CIBP AT 4700' WITH 2 SX CEMENT ON TOP WITH BAILER. 2ND PLUG SPOT 50 SX CEMENT

AT 600'. 3RD PLUG SPOT 50 SX CEMENT AT 340'. 4TH PLUG SPOT 10 SX AT 0-40'. USED 8 SX

FOR GEL SPACER. GOOD CIRCULATION THROUGHOUT JOB.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 04 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP @ 4700' WITH 2 SX CEMENT ON TOP WITH BAILER. 2ND PLUG SPOT 50 SX CEMENT

AT 600'. 3RD PLUG SPOT 50 SX CEMENT AT 340'. 4TH PLUG SPOT 10 SX CEMENT AT 0-40'. USED

8 SX FOR GEL SPACER. GOOD CIRCULATION THROUGHOUT JOB.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2625' OF 5/8" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID)OBSERVE THIS PLUGGING.

INVOICED

DATE 8/18/00 SIGNED

(TECHNICIAN)

FORM CP-2/3

INV. NO. 1060435

Handwritten signatures and initials.