

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-20,212-0000

LEASE NAME Holmes "B"

WELL NUMBER 1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 29 TWP. 33 RGE. 13W (E) or (W)

COUNTY Barber

Date Well Completed         

Plugging Commenced 8-1-00

Plugging Completed 8-4-00

LEASE OPERATOR Great Eastern Energy & Development Corp.

ADDRESS 500 W. Texas, Suite 955, Midland, TX, 79701

PHONE# (915) 682-1178 OPERATORS LICENSE NO. 9449

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by Scott Alberg (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4843'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	342'	None
				5-1/2"	4790'	2625'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from          feet to          feet each s  
Set PB @4700', put 2 sks. cement on top, Shot pipe @3500', 2625', pulled up to 600', pumped  
6 sks. gel, 50 sks. cement, 2 sks. gel, pulled to 340', pumped 50 sks. cement, pulled to 40',  
pumped 20 sks. cement and circulated to surface. 60/40 pos, 6% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mike's Testing & Salvage, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 18th day of August, 2000

[Signature] RECEIVED  
Notary Public STATE CORPORATION COMMISSION

My Commission Expires:         

