

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-007-10332-0000
API NUMBER Drilled 1943

LEASE NAME Lasswell

WELL NUMBER 3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 29 TWP. 33S RGE. 13 ~~06000~~ (W)

COUNTY Barber

Date Well Completed 1943

Plugging Commenced 1-27-98

Plugging Completed 1-29-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Molz Oil Company

ADDRESS RR #2, Box 54, Kiowa, KS 67070

PHONE# (316) 296-4558 OPERATORS LICENSE NO. 6006

Character of Well good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-27-98 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? no If not, Is well log attached? no

Producing Formation Snyderville Depth to Top 4007 Bottom 4010 T.D. 4175 CIBP

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4	290	None
				7"	4900	562

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.
Lay down 2 3/8 tubing, set CIBP at 3950, dump 7sx portland cement with dump bailor, stretch and cut pipe at 562, lay down casing, run 2 3/8 tubing to 560, pump 10sx jell and 75sx cement, pull tubing to 311, spot 75sx cement, pull tubing to 60, pump 30sx cement and circulate to surface. 60/40 6% jell

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Molz Oil Company

STATE OF Kansas COUNTY OF Barber, ss.


Alan Vratil (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

2-17-98

(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 14 day of February, 1998

Glenda Morrison
Notary Public

My Commission Expires: 10/14/98