

15-007-10332 -0000

To: 1,052221
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Drilled 1943
C NW, SEC. 29, T 33 S, R 13 W/R
3960 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 6006
Operator: Molz Oil Company
Name: RR 2, Box 54
Address: Kiowa, KS 67071

Lease Name Lasswell Well # 3
County Barber 161.79
Well Total Depth 4978 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 290

Abandoned Oil Well Gas Well X Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 2 p.m. Day: 29 Month: 1 Year: 19 98

Plugging proposal received from Alan Vratil
(company name) Clarke Corporation (phone) 316-885-5665

were: 7" at 4900', CIBP at 4715', Perfs at 4007-10'
1st plug set CIBP at 3950' with 7 sx cement on top,
2nd plug pump 10 sx gel and 75 sx cement at 560',
3rd plug pump 75 sx cement at 300',
4th plug at 60-0' with 25 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 3:30 p.m. Day: 29 Month: 1 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3950' and dumped 7 sx cement on top,
2nd plug ran tubing to 560' and pumped 10 sx gel and 75 sx cement,
3rd plug pulled tubing to 300' and pumped 75 sx cement,
4th plug pulled tubing to 60' and pumped 20 sx cement.

Good circulation.
RECEIVED KANSAS CORPORATION COMMISSION
FEB 03 1998
2-3-98
CONSERVATION DIVISION WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 560' of 7" casing.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.
DATE FEB 05 1998
INV. NO. 50032
Signed Richard M. Lucy (TECHNICIAN)