

2 040263

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-077-21088-60-00

TECHNICIAN'S PLUGGING REPORT

SW/SE/NE, SEC. 16, T. 35 S, R. 5 W  
2970 feet from N/2 section line  
990 feet from W/2 section line

Operator License # 5230 Lease Name C.D. Williams Well # C-1  
Operator: Petroleum Energy Inc. County Harper 168.48  
Name & Address 234 E. Douglas St. 350 Well Total Depth 5184 feet  
Wichita Ks. 67202 Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 595

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Chase Ks.

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Vernon Duce

(company name) Kelso Casing (phone) \_\_\_\_\_

were: 5 1/2 5184 sand to 4980' SKS  
Perf 5030-60 3 hull, 15 gel, 115 SKS

STATE CORPORATION COMMISSION  
APR 25 1986  
4-25-86  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by St. U. Sun  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 1415 Day: 16 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT The well was sandced off to 4980'  
to cover perforations and capped with 6 sks of cement  
The 5 1/2" casing was shot off and recovered from  
4000' The Top was squeezed thru the 8 5/8" casing by  
pumping 3 sks of hulls, 15 sks of gel, 95 sks of cement  
a wiper plug and 20 sks of cement.

Remarks: Allied # 2328 MX 1100 # SI 500 #  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 25 1986  
INV. NO. 13539

Signed St. U. Sun  
(TECHNICIAN)