

2 040264

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-077-21083-00-00

NE 1/4 SEC. 16, T. 35 S. R. 5 (ND)

2310 feet from A/S section line

330 feet from B/B section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5230

Lease Name C.D. Williams Well # B-1

Operator: Petroleum Energy Inc.

County Harper 167.54

Address 224 E. Douglas

Well Total Depth 5155 feet

Sut 350

Conductor Pipe: Size _____ feet

Wichita Ks 67202

Surface Casing: Size 8 7/8 feet 607

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase Ks

Company to plug at: Hour: _____ Day: _____ Month: _____

Plugging proposal received from Vernon Dunce

(company name) Kelso Casing Pulling

STATE CORPORATION COMMISSION
APR 25 1986
4-25-86
CONSERVATION DIVISION
Wichita, Kansas

were:

5 1/2 5155 Sand to 4975 d to sks

Perf 5026-64 3 Hull 15 gel 115 sks.

Plugging Proposal Received by St. V. Sun
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 1300 Day: 16 Month: 4 Year: 1985

ACTUAL PLUGGING REPORT The 4 1/2" casing was sandbed back

to 4975' and capped with 6 sks of cement. The 5 1/2"

casing was shot off and recovered from 4000'. The top

was squeeze plugged thru the 8 7/8" casing by pumping

3 sks of hulls, 15 sks of gel and 95 sks of cement, a wiper

plug and 20 sks of cement.

Remarks: Albid # 2329 MX 800 # SI 400 #

(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE APR 25 1986

Signed St. V. Sun
(TECHNICIAN)

INV. NO. 13541

RP