

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 23 1963
 9-23-63

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Deacon of Forbes Casing Pulling Inc. has this date requested permission to plug the following described well:

Mr. Deacon guarantees payment of the plugging fee.

Operator's full Name: Amerada Petroleum Corporation

Complete Address: Box 197, Great Bend, Kansas

Lease Name: Edd Sterling Well No. # 1

Location: C NW NW Sec. 35 Twp. 34 Rge. 13 (E) (W) W

County Barber Total Depth 3608 Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Deacon was instructed to plug the well as follows:

298' of 8 5/8" surface pipe, cemented to top. 3608' of
5 1/2" long string, cemented with 150 sacks. Top perforation
3595'. Bottom hole sanded to 3580', cemented with 5 sacks.
Fill hole with mud to 275', 10' rock bridge, cement with
20 sacks. Fill hole with mud to 40', 10' rock bridge, cement
with 10 sacks to base cellar.

Very truly yours,

Achie Elving
 Conservation Division Agent