

State of Kansas



15-007-20367-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

WICHITA, KANSAS

New Address
245 North Water
Wichita, Kansas 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cameron of H-30 Drlg Co has this
date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: National Oil Co

Complete Address: Suite 550 OW Garvey Bldg Wichita, KS

Lease Name: Knackstedt Well No. 1

Location: N/2 NW Sec. 18 Twp. 30s Rge. 13 (E)(W) W

County: Barber Total Depth 4770 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cameron was instructed to plug the well as follows:

372 ft 8 5/8 surface cemented with 300 sacks. Pump plug,

35 sacks cement to 350 ft. Mud to 40 ft, plug, 1/2 sack

hulls, 15 sacks cement to surface. 2 sacks cement in

rat hole.

Pumped by Halliburton Cementing Great Bend FEB 9 1976

Very truly yours,
CONSERVATION DIVISION
Wichita, Kansas

Russell H. Behtem
Conservation Division Agent