

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 20 1965

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Sept. 15, 1965

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Bill Musgrove of Bowers Drilling Co. has this
 date requested permission to plug the following described well:

Mr. Bill Musgrove guarantees payment of the plugging fee.

Operator's full Name: Rains & Williams Oil Co.

Complete Address: 1425 Plaza Building Wichita, Kansas.

Lease Name: Lenkner Well No. #1

Location: C-NW-NE Sec. 19 Twp. 30S Rge. 13 (E) (W) X

County Barber Total Depth 4602' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bill Musgrove was instructed to plug the well as follows:

350 ft. Of 8 5/8" surface pipe circulated with cement.
Mud to 300 ft. cementing plug, 1/2 sack hulls, 30 sacks cement,
hole filled to 50 ft. with mud, cementing plug, 1/2 sack hulls,
10 sacks cement to base of cellar by Globe Cementing Co.
2 sacks cement in rat hole.

Very truly yours,

Herman Justus
 Conservation Division Agent