



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 13 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Mossaman of Thomas Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Mossaman guarantees payment of the plugging fee.

Operator's full Name: National Oil Co.

Complete Address: 200 W Douglas Suite 550 Wichita, Ks

Lease Name: Lemon Well No. 1

Location: NE/NW Sec 17 Twp. 30s Rge. 13 (E)(W) W

County: Barber Total Depth 4780 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Mossaman was instructed to plug the well as follows:

309 ft 8 5/8 surface pipe cemented with 300 sacks. Pump

30 sacks cement to 300 ft. Mud to 40 ft, plug, 1/2 sack

hulls, 13 sacks cement to surface. 2 sacks cement in rat

hole.

Pumped by Halliburton Cementing Co. Great Bend, Ks

Very truly yours,

Conservation Division Agent