



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
10-13-72  
OCT 13 1972

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Buffington of Red Tiger Drlg. Co has this

date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Glen N. Rupe

Complete Address: 925 O.W. Garvey Bldg Wichita, Ks

Lease Name: Lemon Well No. 1

Location: 20 ft W of SW/SE Sec. 17 Twp. 30s Rge. 13 (E)(W) W

County: Barber Total Depth 4650 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Buffington was instructed to plug the well as follows:

Set 90 ft 13" conductor string. 1014 ft 8 5/8 surface  
pipe cemented with 420 sacks. Fill hole to 800 ft, plug,  
1/2 sack hulls, 40 sacks cement. Mud to 60 ft, plug, 1/2 sack  
hulls, 15 sacks cement to surface. 2 sacks cement in  
rat hole.

Very truly yours,

H. Russell Bihunter  
Conservation Division Agent