

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed August 22, 1967.

Dear Sir:

Mr. A. C. Bowman of Barbara Oil Company has this
date requested permission to plug the following described well:

Mr. Bowman guarantees payment of the plugging fee.

Operator's full Name: Barbara Oil Company

Complete Address: 509 Union Center Bldg., Wichita, Kansas 67202

Lease Name: F. W. Storm Well No. # 1

Location: C NW NW Sec. 18 Twp. 33 Rge. 13 (E)(W) W

County Barber Total Depth 5205' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bowman was instructed to plug the well as follows:

219' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fill
hole with drilling mud to 210', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of collar bridge and cement rat hole with 2 sacks.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

SEP 12 1967
9-12-67
CONSERVATION DIVISION
Wichita, Kansas

Audie Elving
Conservation Division Agent