

15-007-20001-00-00

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 27 1967  
1-17-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill, Filed  
January 3, 1967

Dear Sir:

Mr. Gerd Steincamp of Strata Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: California Time Petroleum, Inc.

Complete Address: P. O. Box 8124, Wichita, Kansas

Lease Name: House Well No. # 1

Location: C SW SW Sec. 15 Twp. 30 Rge. 12(E)(W) W

County Barber Total Depth 4476' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

310' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40, 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Audie Elving  
Conservation Division Agent