

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM

(To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 4 1962
 9-4-62
 CONSERVATION DIVISION
 WICHITA, KANSAS

Dear Sir:

I have this date 8-27-62, 1962, authorized
 the following plugging operation:

Operator's full Name: Petroleum, Inc.
 Complete Address: Rural Route #2 Great Bend, Kansas
 Lease Name: Roberts Well No. 1
 Location: NE NE SW Sec. 34 Twp. 34 Rge. 13 (E) (W) X
 County Barber Total Depth 4910'
 Oil Well Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated: Abandoned Oil Well

Operator was instructed to plug well as follows:

Present T.D. 3725' . Casing perforated at 3662- 3672' .
Sanded back to 3650' and 5 sacks cement. 265' of 8-5/8"
surface pipe circulated with 225 sacks cement. Hole filled to
250' with mud, 10' rock bridge and 20 sacks cement. Hole
filled to 30' with mud, 10' rock bridge and 10 sacks
 cement to bottom of cellar.

Very truly yours,

Herman J. Gustas
 Conservation Division Agent