

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 27 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Gene Mort of Helmerick & Payne Inc. has this

date requested permission to plug the following described well:

Mr. Mort guarantees payment of the plugging fee.

Operator's full Name: Helmerick & Payne Inc.

Complete Address: Box 558, Garden City, Kansas

Lease Name: Kumberg Well No. # 1

Location: NW NW SW Sec. 11 Twp. 30 Rge. 12 (E) (W) W

County Barber Total Depth 4700 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mort was instructed to plug the well as follows:

290' of 8 5/8" surface pipe, cement circulated with 225
sacks. Fill hole with mud to 220', 1st cementing plug,
1/4 sack hulls, cement with 25 sacks. Fill hole with mud
to 40', 2nd cementing plug, 1/4 sack hulls, cement with 15
sacks to base cellar. Rat hole bridged and cemented with
2 sacks.

Very truly yours,

Audie Elving
 Conservation Division Agent