

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Rankin of Sage Drlg Co has this
date requested permission to plug the following described well:

Mr. Rankin guarantees payment of the plugging fee.

Operator's full Name: G.N. Rupe

Complete Address: 925 O.W. Garvey Bldg Wichita, KS

Lease Name: Hamilton Well No. 1

Location: SW/NW Sec. 11 Twp. 30S Rge. 12 (E)(W)W

County: Barber Total Depth 3550 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rankin was instructed to plug the well as follows:

287 ft 8 5/8 surface cemented with 300 sacks. Fill hole
to 240 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud to
40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

Russell B. Bickert
Conservation Division Agent