

15-007-20039-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed August 29, 1967.

Dear Sir:

Mr. A. G. Radke of Garvey Drilling Company has this
date requested permission to plug the following described well:

Mr. Radke guarantees payment of the plugging fee.

Operator's full Name: W. C. Payne

Complete Address: 800 United Founders Tower, Oklahoma City, Okla.

Lease Name: Gibson Well No. # 1

Location: C NE SW Sec. 3 Twp. 30 Rge. 12 (E)(W) W

County Barber Total Depth 4707' ~~5707'~~ Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Radke was instructed to plug the well as follows:

378' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fill
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 20 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 8
sacks to base of cellar, ~~in field~~ and cement rat & mouse holes with 4 sac

STATE CORPORATION COMMISSION

SEP 15 1967

Very truly yours,

CONSERVATION DIVISION
Wichita, Kansas

Audie Elving
Conservation Division Agent